BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of work:Providing,laying and Repairs of name boards in Veerannapalya, Kariyanna Layout, Mariyannapalya, Kempapura and Surrounding areas of ward no.07, Byatarayanapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	158.4	KSRRB M800-3. Direction and place identifcation signs upto 0.9 sqm size Board. Providing and erecting direction and place identifcication retro reflectorised signs as per revised IRC 67-2012, made of high density grade sheeting vide clause 800.13 fixed over aluminium sheeting 2mm thick with area not exceeding 0.9 sqm supported on a mild steel single angle iron post 75x75x6mm firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 45x45x60cm , 60cm below ground level as per approved drawing complete as per specifications. MORTH Specifications, No.801, Type IV Sheeting(Page No. 179, Item No. 24.3.1)	Sqm	7111.8	
2	32	Providing RCC Ornamental Name Boards (Data Rate Name Boards	Nos	8000	
3	1075	Providing and Laying Ready Mix Priming Coat Overnew Steel or other metal surface including preparing the surface after throughly cleaning of oil grease dirt and other froeign matter ans sand papering cost of materials labour as per specifications (Page No:120,Item No:15.73_	Sqm	28	
4	16588	Supply MS Pipe Code No:267.Sl No 301,Pg No.XO.PWD SR 15-16	Rmtr	48	
5	1408.78	KSRRB M800-7. Painting on Steel surface :- Providing and applying two coats of ready mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications. Complete as per specifications. MORTH Specification No.803(page no.180, item no.24.8.1)	Sqm	59.4	
6	220500	Painting new latter and figures any shade with synthetic enamel paint black or any approvel colour to give an even shede complete as per specification (I) Hindi (Matras commas and the like not to be measured and paid for half latter shall be counted as half) (page no.181, item no.24.9)	Cum	0.76	
7	158.4	Conveying the excavated debries and over burden earth etc., to a lead of 10.00 Km distance by using private vehicle this includes the cost of loading and unloading charges etc., complete.	Per Cum	94.82	

No of corrections - Nil

12/01

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

12/01

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

Chief Engineer
Yelahanka Zone
North Bangalore Mahanagara
Palike
Bangalore 92

12.01.17